

Jackson Municipal Airport Authority
Relocation of Taxiway Bravo at Hawkins Field Airport - Rebid
FAA AIP Grant No. 3-28-0038-025-2021

Pay Item	Description	Quantity	Unit	Unit Price	Total
	BASE BID				
C-105-5.1	Mobilization	1	LS		
P-101-5.1	Concrete pavement removal	820	SY		
P-101-5.2	Asphalt overlay concrete removal	5680	SY		
P-150-4.1	Site Demolition, Complete	1	LS		
P-152-5.1	Earthwork	1	LS		
P-152-5.2	Undercut	200	CY		
P-152-5.4	Granular backfill for Undercut	200	CY		
P-155-8.1	Lime-Treated subgrade	2790	SY		
P-401-8.1	3" P401	560	Ton		
P-602-5.1	Emulsified Asphalt Prime Coat	900	Gal		
P-209-5.1	8" P209	2790	SY		
D-705-5.1	4" Perforated Underdrain	515	LF		
D-705-5.2	4" Non-perforated underdrain outfall pipe	40	LF		
D-705-5.4	Underdrain Clean out	7	EA		
D-705-5.5	Underdrain endwall	1	EA		
D-752-5.2	Headwall for 24" pipe	2	EA		
D-701-5.1	24" CL V RCP	136	LF		
D-754-5.1	2' Concrete Swale	1135	LF		
C-102-5.1	Construction entrance	1	LS		
C-102-5.2	Silt fence	400	LF		
C-102-5.3	Inlet protection	1	EA		
C-102-5.4	Rock filter ring	1	EA		
C-102-5.5	Rock check dam	1	EA		
C-102-5.6	12" sediment tube	635	LF		
C-102-5.7	20" sediment tube	240	LF		
P-602-5.1	Reflective Pavement Marking	4200	SF		
P-620-5.2	Existing Paint Marking Removal	1	LS		
L-108-5.1	No. 8 AWG, 5kV, L-824, Type C Cable, Installed in trench, ductbank or conduit	1	LS		
L-110-5.1	Install 2" PVC Schedule 40 conduit in trench including excavatiron and backfill	1	LS		
L-115-5.1	Install L-867D Electrical hand hole including concrete encasement, grounding and appurtenances	13	EA		
L-115-5.2	Remove Existing L-867D Electrical Handhole	17	EA		
L-125-5.1	Remove Existing MIRL/MITL Threshold light and Transformer and save for Re-installation or deliver to airport. Demolish existing edge light maintenance pad and base can	17	EA		
L-125-5.2	Install MIRL/MITL/Threshold light, transformer, and base can in asphalt including sawcut and pavement repair	14	EA		

Jackson Municipal Airport Authority
Relocation of Taxiway Bravo at Hawkins Field Airport - Rebid
FAA AIP Grant No. 3-28-0038-025-2021

Pay Item	Description	Quantity	Unit	Unit Price	Total
L-125-5.5	Remove Existing Base Mounted sign L-858 and save for reinstallation or deliver to airport, demolish concrete base and appurtenances	2	EA		
L-125-5.6	Reinstall existing base-mounted sign L-858 to new base can and concrete pad	2	EA		
T-905-5.1	4" Topsoil	18500	SY		
T-904-5.1	Sod	18500	SY		
TOTAL BASE BID					
Pay Item	Description	Quantity	Unit	Unit Price	Total
	ALTERNATE BID				
P-101-5.1	Concrete pavement demo	12000	SY		
P-150-4.1	Miscellaneous demolition	1	LS		
P-152-5.1	Earthwork	1	LS		
D-752-5.1	Flared end section for 15" pipe	1	EA		
D-701-5.1	15" CL V RCP	63	LF		
D-754-5.1	2' Concrete Swale	890	LF		
C-102-5.2	Silt fence	1780	LF		
C-102-5.3	Inlet protection	7	EA		
C-102-5.4	Rock filter ring	1	EA		
T-905-5.1	4" Topsoil	15000	SY		
T-904-5.1	Sod	15000	SY		
TOTAL ALTERNATE BID					
TOTAL BID AMOUNT (BASE + ALTERNATE)					